

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE	PAGE 1 OF 4 PAGES
2. AMENDMENT/MODIFICATION NO. AMENDMENT NO. 0001		3. EFFECTIVE DATE 02/26/08	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. (If applicable) 08-0436	
6. ISSUED BY Resident Officer in Charge of Construction 1005 Michael Road Camp Lejeune, NC 28547-2521		CODE mks	7. ADMINISTERED BY (If other than Item 6) See Item 6		CODE
8. NAME AND ADDRESS OF CONTRACTOR (No., street, county, State and ZIP Code)				(X)	9A. AMENDMENT OF SOLICITATION NO. N40085-08-R-0436
				X	9B. DATED (SEE ITEM 11) 02/25/08
					10A. MODIFICATION OF CONTRACT/ORDER NO.
					10B. DATED (SEE ITEM 11)
CODE		FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor is not, is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

08-0436, Messhall Loading Zone Overlays

1. Delete the original Scope of Work in its entirety and replace with the attached REVISED Scope of Work.

(CONTINUED)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
15B. CONTRACTOR/OFFEROR		16B. UNITED STATES OF AMERICA	
15C. DATE SIGNED		16C. DATE SIGNED	
(Signature of person authorized to sign)		(Signature of Contracting Officer)	

N40085-08-B-0436
FC-420 Loading Zone Overlay
WO# 4127623
M1 Project # 8M032CN
Prepared By: Matthew O'Leary

REVISED Scope of Work

General Description: The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

This scope of work is to be accomplished at FC-420 Loading Zone (see site plan). Remove existing damaged asphalt in loading zone area approx 770 SY. Provide a 2.5 inch binder and a 2" wearing course of S-9.5B Superpave asphalt (NCDOT compliant) approx 770 SY. The contractor shall make a site visit to accurately determine the materials, equipment, and labor needed to complete the job. The measurements furnished here are for reference only. The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

Detailed requirements and specifications:

Pave Entire Loading Zone behind FC-420 (per site plan):

1. Remove existing asphalt approx 770 SY. Clean the designated area, and prep for new asphalt.
2. Provide a 2.5 inch binder.
3. Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91%. The total area to be resurfaced is approximately 770 SY.
4. Place Superpave wear surface to achieve a 2 inch compacted depth.
5. Provide for a smooth transition from existing road surfaces to the newly paved areas.
6. All paved areas shall be graded to allow a minimum 2% slope toward existing drainage.
7. Any disturbed areas shall be backfilled with top soil, raked, and seeded with Coastal Lawn Mix at a rate of 5 pounds per 1,000 square feet. Clean up and haul off all debris and soil/rock materials at the site.

Special Requirements: The building will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity. The Point of Contact at the work site for this project is Mickey Hatfield 451-7561. Make arrangements with the POC one week prior to the project start date so vehicles can be moved and work can commence.

N40085-08-B-0436
Bldg 411 Loading Zone Overlay
WO# 4127623
M1 Project # 8M032CN
Prepared By: Matthew O'Leary

REVISED Scope of Work

General Description: The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

This scope of work is to be accomplished at Bldg 411 Loading Zone (see site plan). Provide wedging / leveling of low areas. Provide a 2 inch wearing course of S-9.5B Superpave asphalt.(NCDOT compliant) approx 465 SY. The contractor shall make a site visit to accurately determine the materials, equipment, and labor needed to complete the job. The measurements furnished here are for reference only. The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

Detailed requirements and specifications:

Pave Entire Loading Zone behind Bldg 411 (per site plan):

1. Provide wedging /leveling of low areas.
2. Apply a tack coat at the manufacturer's specifications on the existing asphalt to be overlaid.
3. Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91%.
The total area to be resurfaced is approximately 465 SY.
4. Place Superpave wear surface to achieve a 2" compacted depth.
5. Provide for a smooth transition from existing road surfaces to the newly paved areas.
6. All paved areas shall be graded to allow a minimum 2% slope toward existing drainage.
7. Restripe loading zone to match existing layout.
8. Any disturbed areas shall be backfilled with top soil, raked, and seeded with Coastal Lawn Mix at a rate of 5 pounds per 1,000 square feet. Clean up and haul off all debris and soil/rock materials at the site.

Special Requirements: The building will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity. The Point of Contact at the work site for this project is Mickey Hatfield 451-7561. Make arrangements with the POC one week prior to the project start date so vehicles can be moved and work can commence.

N40085-08-B-0436
Bldg FC-303 Loading Zone Overlay
WO# 4127623
Project # 8M032CN
Prepared By: Matthew O'Leary

REVISED Scope of Work

General Description: The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

This scope of work is to be accomplished at Bldg FC-303 Loading Zone (see site plan). Remove existing damaged asphalt in loading zone area approx 1478 SY. Provide a 2.5 inch binder and a 2 inch wearing course of S-9.5B Superpave asphalt.(NCDOT compliant) approx 1478 SY. The contractor shall make a site visit to accurately determine the materials, equipment, and labor needed to complete the job. The measurements furnished here are for reference only. The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

Detailed requirements and specifications:

Pave Entire Loading Zone behind Bldg FC-303 (per site plan):

1. Remove existing asphalt approx 1478 SY. Clean the designated area, and prep for new asphalt.
2. Provide a 2.5 inch binder.
3. Provide a 2 inch wearing course of S-9.5B Superpave asphalt (NCDOT compliant) compacted to 91%. The total area to be resurfaced is approximately 465 SY.
4. Place Superpave wear surface to achieve a 2 inch compacted depth.
5. Provide for a smooth transition from existing road surfaces to the newly paved areas.
6. All paved areas shall be graded to allow a minimum 2% slope toward existing drainage
7. Restripe Loading Zone to match existing layout.
8. Any disturbed areas shall be backfilled with top soil, raked, and seeded with Coastal Lawn Mix at a rate of 5 pounds per 1,000 square feet. Clean up and haul off all debris and soil/rock materials at the site.

Special Requirements: The building will remain in operation during the entire construction period. The contractor shall conduct their operations so as to cause the least possible interference with normal operations of the activity. The Point of Contact at the work site for this project is Mickey Hatfield 451-7561. Make arrangements with the POC one week prior to the project start date so vehicles can be moved and work can commence.