

CONTRACT #: N40085-10-B-0413
PROJECT #: 10M017CN
MACC #: 10-0413
MAXIMO#: 4247864

TITLE: THERMOPLASTIC CROSSWALKS

ATTACHMENTS:

1. Site Plan

SCOPE OF WORK: The contractor shall provide all material, labor, equipment and supervision required to accomplish the following:

General description – The contractor shall:

Remove any existing road markings (as indicated on the site plan) and install thermoplastic crosswalks and road markings at the locations listed in this scope and on the attached site plan.

Detailed requirements and specifications:

- All markings to be installed shall be “Thermoplastic” and shall comply with the 2006 NCDOT ROADWAY STANDARDS DRAWINGS.
- Completely remove any existing road markings by means that causes the least amount of damage to the pavement.
- Note: The two crosswalks on Seth Williams Blvd. shall be installed first before any other work is performed.

The contractor shall:

- Install an N.C.D.O.T. compliant “High Visibility” crosswalk across Seth Williams Blvd. adjacent to Wavell St. as shown on the site plan.
- Install an N.C.D.O.T. compliant “High Visibility” crosswalk across Seth Williams Blvd. adjacent to Winston Rd. as shown on the site plan.
- At the intersection of McHugh Blvd. and Cross St., located on Cross St., remove the stop bar/line and road lines and install a new stop bar rearward at the traffic light to accommodate a crosswalk connecting the bike path across Cross St. The stop bar shall be no closer than 4 feet to the new crosswalk.

- Install an N.C.D.O.T. compliant “High Visibility” crosswalk connecting the bike path across Cross St. at the McHugh Blvd. intersection.

SUBMITTALS: None

SPECIAL SCHEDULING AND ACCESS:

The contractor shall provide traffic control (i.e. cones, flagman, signs, etc.) sufficient to prevent injury to personnel, damage to property, and allow for safe flow of traffic.

Prior to detouring or re-routing traffic, the contractor shall contact Mr. Cekloski., ISS Operations Chief, at 451-0146.

SPECIAL CONDITIONS: None

HAZARDOUS MATERIALS: None Identified

ENVIRONMENTAL: None



New
Crosswalk

New
Crosswalk

**10M017CN
4247864**

**Thermoplastic
“High Visibility”
Crosswalks**

**Approx. 27’
Across Road**

**Crosswalks
= to be
Installed**



4247864

Thermoplastic
"High Visibility"
Crosswalks

Approx. 48'
Across Road



Remove Existing
Road Markings

Remove Existing
Road Markings

— = Stop Bar
to be
Installed

▨ = Crosswalk
to be
Installed
→ N