

**AASF Addition  
McEntire JNGB**

**Date: 5-25-2010**

**Addendum Items Previously Sent:**

1. Specification Section 074216, Par. 2.1, B, 1: Change "Stainless Steel Sheet" to Galvanized Steel Sheet. In Par. 2.1, B, 2: Change "Satin, Flat Finish" to "Powdercoat Finish".
2. Specification Section 074213, Par. 2.4,B: Omit " with flush joint between soffit panels"
3. Provide temporary security at location shown on the attached **updated** drawing C101-SUPPLEMENTAL DRAWING. Fence shall be 6 foot tall chain link topped with 3 strands of barbed wire. Construction details of temporary fence shall be the same as shown on drawings for permanent fence. At completion of construction, the temporary fencing shall be completely demolished and removed from the construction site, holes shall be filled and all patching be completed with materials matching adjacent materials.

**Addendum Items New Herewith:**

4. Provide roof drains and associated piping, tapered insulation and roofing patching as shown on the attached "**Supplemental Roof Plan**".
5. Specifications Section 074113, Page 6, Par I and I.1: Omit these paragraphs entirely.
6. Item No. 1 above: Change "Powdercoat" to "Kynar 500 or equal".
7. Section 334001, Stormwater Treatment Specification.
8. General Notes for 5/E311 (Question # 213).