KEYNOTES:

1. INSTALL NEW PRESSURE TREATED TIMBER AND GRAVEL STEPS IAW DETAIL A/C621.
2. INSTALL SIDEWALK FLUSH WITH PAVEMENT.
3. TIE NEW SIDEWALK INTO EXISTING SIDEWALK.
4. INSTALL RAISED PLANTER IAW LANDSCAPE DRAWINGS.
5. INSTALL NEW RAMP AND HANDRAIL IAW DETAIL B/C621.
6. INSTALL TEMPORARY ASPHALT AND CONCRETE SIDEWALK FOR CONSTRUCTION ACCESS. REMOVE TEMPORARY ASPHALT AND HANDICAP RAMPS AFTER CONSTRUCTION IS COMPLETE. RESTORE CURB AND GUTTER AND SIDEWALK TO ORIGINAL LOCATIONS IAW DETAILS B/C620, D/C620, & E/C620.
7. COMPLETE CONSTRUCTION OF SIDEWALK TO MEDIA CENTER PATIO, TRACK PATIO, AND STEPS TO TRACK PRIOR TO CLOSING EGRESS OUT OF EXISTING BUILDING.

CIVIL LEGEND – SITE

- 4" CONCRETE SIDEWALK – INSTALL IAW DETAIL A/C620.
- 6" GRAVEL ACCESS DRIVE – INSTALL IAW DETAIL C/C620.
- CJ — CONTRACTION JOINT – INSTALL IAW DETAIL A/C620.
- EJ — EXPANSION JOINT – INSTALL IAW DETAIL A/C620.
- BID OPTION: SIDEWALK IMPROVEMENTS
- CONSTRUCTION LIMITS

BALL FIELD

BLEACHER

DUGOUT

Bleacher

BALL FIELD

BLEACHER

DUGOUT

DUGOUT

EXISTING GRAVEL

EXISTING GRAVEL

CTION LIMITS

SHED

LIMITS OF DISTURBANCE

82' FORCE PROTECTION LIMITS

EXISTING RAMP

EXISTING MODULAR CLASSROOM

EXISTING RAMP

EXISTING MODULAR CLASSROOM

12'

12'

5' SIDEWALK

MECH

MATCHLINE
SEE SHEET C200

GRAPHIC SCALE

20 0 10 20 40 80

(IN FEET)
1 inch = 20 ft.

STATE PLANE

NORTH CAROLINA PROFESSIONAL SEAL 027779 ENGINEER LAWRENCE K. BARTHELEMY, IV

US ARMY CORPS OF ENGINEERS SAVANNAH

BY	DATE	DESCRIPTION	SYMBOL

DESIGNED BY: JBS
DRN BY: JDG
SUBMITTED BY: LKB
FILE NAME: BRHC-200.DWG
SIZE: 34x22
CKD BY: LKB
PLOT SCALE: 1" = 20'
DATE: 25 JAN 2010
SOLICITATION NO.: W912HN-09-R-0018
CONTRACT NO.:
CATEGORY CODE: 730-46-01
PLOT DATE:

U. S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
SAVANNAH DISTRICT

LS3P ASSOCIATES LTD.
205 ½ KING STREET
CHARLESTON, SC. 29401

ALBRITTON JUNIOR HIGH SCHOOL ADDITION
FT BRAGG NORTH CAROLINA

SITE IMPROVEMENTS PLAN

PLATE REFERENCE NUMBER
C-201
SHEET 10