

PLANT BED NOTES FOR CONCRETE PLANTER

1. CONTRACTOR SHALL PREPARE PLANTING SOIL MIX AND PROVIDE PINETRAW MULCH, AND THE BED SHALL BE CROWNED IN THE MIDDLE 6" HIGHER THAN THE EDGE OF THE BED.
2. INSTAL ROOTGEL (WWW.ROOTGEL.COM), OR APPROVED EQUAL, GRANULAR INTO THE EXCAVATED SOIL, SAVING A SMALL AMOUNT OF UNTREATED SOIL. THEN PLACE THE ROOTBALL INTO THE HOLE AND FILL AROUND THE ROOTBALL WITH THE SOIL AND ROOTGEL COMBINATION. TOP OFF WITH UNTREATED SOIL.



US ARMY CORPS OF ENGINEERS SAVANNAH

SYMBOL	DESCRIPTION	DATE	BY

DESIGNED BY: JDC	DATE: 25 JAN 2010
DWN BY: GBS	SOLICITATION NO.: W912M-09-R-0018
CHK BY: LKB	CONTRACT NO.:
SUBMITTED BY: LKB	CATEGORY CODE: 730-46-01
FILE NAME: BRHL-301.DWG	PLOT DATE:
SIZE: 34x22	PLOT SCALE:

U. S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
SAVANNAH DISTRICT
LS&P ASSOCIATES, LTD.
205 1/2 KING STREET
CHARLESTON, SC 29401

ALBRITTON JUNIOR HIGH SCHOOL ADDITION
FT BRAGG NORTH CAROLINA
LANDSCAPE PLAN

PLATE REFERENCE NUMBER
L-102
SHEET 28

