KEYED NOTES

1. GYPSUM BOARD BULKHEAD @ 9'-0" AFF. SEE DETAIL B/A305.
2. ALIGN CEILING GRID WITH EXISTING CEILING. NEW CEILING HEIGHT TO MATCH EXISTING.
3. CMU BULKHEAD @ 7'-4" AFF.
4. REPAIR EXISTING CEILING SUSPENSION SYSTEM AND REPLACE ANY CEILING TILES DAMAGED BY CONSTRUCTION AND DEMOLITION OF TEMPORARY CORRIDOR.
5. ALL WALLS INDICATED EXTEND TO UNDERSIDE OF ROOF DECK. SEE DETAIL J/305.
6. MOUNT LIGHTS TO BOTTOM OF ROOF TRUSSES.
7. SEE MECH DRAWINGS FOR BOILER FLUE.
8. SEE 1/A403 AND 1/A404 FOR PROJECTION EQUIPMENT NOTES.

LEGEND

- 1 HOUR FIRE RATED PARTITION
- 3 HOUR RATED FIRE WALL
- GYPSUM BOARD CEILING
- STUCCO SOFFIT
- 2'-0"x2'-0" ACOUSTICAL LAY-IN TILE & SUSPENDED GRID. SEE SPECS.
- 1 HOUR FIRE RATED SUB-CEILING AT BOTTOM OF ROOF TRUSSES. (FINISHED CEILING WHERE NOTED ON FINISH SCHEDULE.) SEE DETAIL A/A305.
- 10'-0" — CEILING HEIGHT ABOVE FINISH FLOOR. 10'-0" AFF TYPICAL, UNLESS NOTED OTHERWISE.
- 3"x 4'-0" WIDE SOUND ATTENUATION BLANKETS ABOVE CEILING SYSTEM
- RECESSED LIGHT FIXTURES
- SURFACE MOUNTED LIGHT FIXTURES
- RETURN OR EXHAUST GRILLE
- SUPPLY DIFFUSER
- EXIT SIGN
- SMOKE DETECTOR
- HEAT DETECTOR
- SPEAKER

KEYPLAN & GRAPHIC SCALE



5' 0' 5' 10' 15' 20' 25'
1/8"=1'-0"

US ARMY CORPS OF ENGINEERS SAVANNAH

SYMBOL	DESCRIPTION	DATE	BY

DESIGNED BY: SCD
DWN BY: SCD
CKD BY: SCD
SUBMITTED BY: -
FILE NAME: -
SIZE: 34x22
PLOT SCALE: As indicated
DATE: 25 JAN 2010
SOLICITATION NO.: W912HN-09-R-0018
CONTRACT NO.:
CATEGORY CODE: 730-46-01
PLOT DATE:

U. S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
SAVANNAH DISTRICT

LS3P ASSOCIATES LTD.
205 ½ KING STREET
CHARLESTON, SC 29401

ALBRITTON JUNIOR HIGH SCHOOL ADDITION
FT BRAGG NORTH CAROLINA

REFLECTED CEILING PLAN

PLATE REFERENCE NUMBER
A-102
SHEET 42