

SECTION 01 14 00

WORK RESTRICTIONS

04/07

PART 1 GENERAL

1.1 SPECIAL SCHEDULING REQUIREMENTS

- a. Permission to interrupt any Activity roads, railroads, and/or utility service shall be requested in writing a minimum of 15 calendar days prior to the desired date of interruption.

1.2 CONTRACTOR ACCESS AND USE OF PREMISES

1.2.1 Activity Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey Activity regulations including safety, fire, traffic and security regulations. Keep within the limits of the work and avenues of ingress and egress. Wear hard hats in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. The Contractor's equipment shall be conspicuously marked for identification.

1.2.1.1 Subcontractors and Personnel Contacts

Furnish a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.2.1.2 Identification Badges

Identification badges will be issued to the Contractor and his employees in accordance with the base security regulations. A copy of the regulations may be obtained from the Provast Marshall Office. Contractor expenses and time to obtain badges will not affect the contract price or time of completion.

1.2.2 Working Hours

Regular working hours shall consist of an 8 1/2 hour period established by the Contractor Officer, Monday through Friday, excluding Government holidays.

1.2.3 Work Outside Regular Hours

Work outside regular working hours requires Contracting Officer approval. Make application 15 calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress, giving the specific dates, hours, location, type of work to be performed, contract number and project title. Based on the justification provided, the Contracting Officer may approve work outside regular hours. During periods of darkness, the different parts of the work shall be lighted in a manner approved by the Contracting Officer.

1.2.4 Occupied and Existing Buildings

The Contractor shall be working in existing buildings or around existing buildings which are occupied. Do not enter the buildings without prior approval of the Contracting Officer.

The existing buildings and their contents shall be kept secure at all times. Provide temporary closures as required to maintain security as directed by the Contracting Officer.

Provide dust covers or protective enclosures to protect existing work that remains and Government material located in the construction site during the construction period.

Relocate movable furniture approximately 10 feet away from the Contractor's working area as required to perform the work, protect the furniture, and replace the furniture in their original locations upon completion of the work. Leave attached equipment in place, and protect them against damage, or temporarily disconnect, relocate, protect, and reinstall them at the completion of the work.

The Government will remove and relocate other Government property in the areas of the buildings scheduled to receive work.

1.2.5 Utility Cutovers and Interruptions

- a. Make utility cutovers and interruptions after normal working hours or on Saturdays, Sundays, and Government holidays. Conform to procedures required in the paragraph "Work Outside Regular Hours."
- b. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.
- c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, compressed air, shall be considered utility cutovers pursuant to the paragraph entitled "Work Outside Regular Hours."
- d. Operation of Station Utilities: The Contractor shall not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor shall notify the Contracting Officer giving reasonable advance notice when such operation is required.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --